
Współrzędne punktów głównych trasy

Projekt :
Plik :Y:\PROJEKTY\2015\Gmina Inowrocław\0106 SIKOROWO-ŁOJEWO\0106_pliki
ulica\0106_NIWELETA_BCH_2015.06.10_poprawne.ulc
Utworzony : data: 2015-06-10 godz. 14:02:30

ZALOM	TYP	WSPÓŁRZĘDNE:	X(N)	Y(E)
PT			5907505,280	3589151,800
W1			5907380,430	3589164,700
		PLK	5907395,334	3589163,160
		SLK	5907380,438	3589164,774
		KLK	5907365,559	3589166,537
Z1			5907172,190	3589190,430
Z2			5907098,320	3589199,370
Z3			5906997,710	3589211,780
W2			5906888,620	3589224,580
		PLK	5906904,967	3589222,662
		SLK	5906889,270	3589226,375
		KLK	5906874,841	3589233,581
W3			5906845,360	3589252,840
		PLK	5906856,779	3589245,381
		SLK	5906844,913	3589249,919
		KLK	5906832,232	3589249,139
W4			5906784,060	3589235,560
		PLK	5906815,735	3589244,489
		SLK	5906783,850	3589239,122
		KLK	5906751,556	3589240,712
W5			5906670,620	3589253,540
		PLK	5906676,622	3589252,589
		SLK	5906670,646	3589252,931
		KLK	5906664,721	3589252,080
KT			5906660,920	3589251,140

 Elementy trasy

ELEMENT	OD	DO			
Prosta	0+000,00	0+110,53	L=110,53m		
Łuk kołowy	0+110,53	0+140,50	R=1500,00m	T=14,98m	B=0,07m
			L=29,97m	g=0,0200rd	g=1,2718g
Prosta	0+140,50	0+335,34	L=194,84m		
Prosta	0+335,34	0+409,75	L=74,41m		
Prosta	0+409,75	0+511,12	L=101,37m		
Prosta	0+511,12	0+604,50	L=93,38m		
Łuk kołowy	0+604,50	0+636,83	R=70,00m	T=16,46m	B=1,91m
			L=32,33m	g=0,4619rd	g=29,4031g
Prosta	0+636,83	0+658,40	L=21,57m		
Łuk kołowy	0+658,40	0+684,01	R=30,00m	T=13,64m	B=2,96m
			L=25,60m	g=0,8534rd	g=54,3308g
Prosta	0+684,01	0+701,15	L=17,14m		
Łuk kołowy	0+701,15	0+765,94	R=150,00m	T=32,91m	B=3,57m
			L=64,79m	g=0,4320rd	g=27,4990g
Prosta	0+765,94	0+841,81	L=75,87m		
Łuk kołowy	0+841,81	0+853,80	R=30,00m	T=6,08m	B=0,61m
			L=11,99m	g=0,3997rd	g=25,4484g
Prosta	0+853,80	0+857,71	L=3,92m		